

Shower Block

Project: Shower Block at Coalmine

Category: Waterproofing

Completion

Date: December 2006

Product: Rhino Linings Duraspray



Job Description

Management of a local coalmine required the shower blocks to be revamped during maintenance shut down.

Both the wall and floor of the shower blocks required lining (a total of 112m square). The job was undertaken in two stages, with the 2 smaller shower blocks completed first, followed by the 3rd shower block.



All areas were washed, cleaned, and acid etched to remove glazing. After masking, 251 Primer was applied followed by Duraspray. Top Coat was then applied along with aggregate for its non slip properties.



To managements satisfaction the job was completed in less then the allotted time frame and prior to the coalmine getting back into full production.