

Butchers Shop

<u>Project:</u> Butchery Shop Floor <u>Category:</u> Slip Resistance/Hygiene <u>Area Covered:</u> 69m²

Completion Date: October 2009
System: Rhino Tuff Stuff,

Rhino Prime SP150 & 251

Job Description

Health Department Regulations require the area to be lined with an easy to clean seamless floor lining. The owners required a solution that met health authority requirements, was durable, would eliminate cracking and flaking, particularly at the wall/floor junction and could provide slip resistant properties. The owner also required a rapid turn around time. An additional benefit of this flooring is the insulating and impact characteristics which reduce worker fatigue.

The area was first washed with a high pressure hot water blaster, to remove layers of failed paint surfaces and animal fats. The area was then ground with a diamond disc to remove the remaining paint and to level the surface as required. The existing floor was creating a pooling effect which was rectified with the use of Ardex K11 self leveling compound. Coving was installed at the wall/floor joins. Rhino Prime SP150 was then rolled onto the floor and wall areas. Rhino Prime 251 was then utilised on the necessary areas. Rhino Tuff Stuff in the colour of Concrete Grey was applied to the substrate incorporating an industrial grade aggregate to provide the slip resistant qualities, then sealed with Rhino top coat.

Rhino Linings' products are environmentally friendly, being solvent free and containing no Volatile Organic Compound's (VOC's) and are certified for use in potable water applications as per Australian Standard and are AQIS accepted

Cool room step before



Cool room step after Tuff Stuff



Processing area before preparation



Processing area after Tuff Stuff





32 Enterprise Crescent, Singleton, NSW, 2330

Tel: 02 6571 2424 Fax: 02 6571 3188 Email: admin@mmaint.com.au

Web: www.rhinolinings.com.au/singleton



Cool room 1 before preparation



Concrete bench before preparation



Cool room 2 before preparation



Floor drain before preparation



Cool room 1 after Tuff Stuff



Concrete Bench after Tuff Stuff



Cool room 2 after Tuff Stuff



Floor drain after Tuff Stuff

