

## Potable Water Storage Tank

**Project:** Remote Community of Imaluk, NT.

**Category:** Primary Containment – Potable Water

**Completion**

**Date:** May 2008

**Product:** TUFF STUFF

**Dealer:** Rhino Linings Top End, Darwin

Before...



### Job Description:

The Potable Water Storage Tank (16.64m dia x 5m high Panel Tank) at this remote NT Community was first installed in 1997 and the lining had commenced failing some time ago. In late 2007 the lining failure had made the tank inoperative and Rhino Linings was asked to offer a spray on seamless lining so that this community could again have a reliable potable water storage facility.

Staff from Rhino Linings Top End and Rhino Linings Australasia Pty Ltd spent approximately 10 days on-site removing the failed liner, grinding and priming the steel surfaces of the tank and spraying TUFF STUFF as a light grey seamless lining over the walls and floor of the tank. Lining integrity at the bolted joint lines on both the floor and wall was a very important consideration when offering a solution to this failed tank liner. The Rhino Linings team provided an economical and technically efficient means of encapsulation, sealing all joints and fittings throughout the tank.

Rhino Linings TUFF STUFF, the long term solution for Potable Water storage facilities.



After...

